

Punjab State Transmission Corporation Limited

From:

Sr. XEN/ P&M
Civil MTC. Division,
Jalandhar.

| | |
|----------------------------|---|
| Limited Tender Enquiry No. | 42/2023-24, 43/2023-24, 44/2023-24, 45/2023-24, 46/2023-24, |
| Date of Receipt of Tenders | 28.08.2023 up to 01:00PM |
| Date of opening of Tenders | 28.08.2023 at 03.00 PM |

To:

M/s As per overleaf.

Memo No 1532/31

Dated 10/08/2020

Subject: Limited TE No.- 42/2023-24 ,43/2023-24 ,44/2023-24 ,45/2023-24 ,46/2023-24.

You are requested to quote your lowest rates for the execution of the following works. Quotations should reach in the Office of the undersigned before 01.00 PM on due date. If this day happens to be a holiday, the quotation can be submitted on the following working day and the same shall be opened on that day. The Quotations received at the above mentioned date and time shall be opened at 03.00 PM in the presence of committee of officers/officials of the department and representatives of the contractors who want to be present.


| Limited TE No. | Description of work | Estimated Cost | Earnest Money (Rs.) | Time for completion of work. |
|----------------|--|----------------|--|------------------------------|
| 42/2023-24 | Repair of store office at 220kv s/s Jamsher. | 2.55 Lakh | 2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000. | 45 Days |
| 43/2023-24 | Repair of control room building at 220kv s/s Chohla sahib. | 2.50 Lakh | 2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000 | 45 Days |
| 44/2023-24 | Repair of CO&C Building & switch house building at 132kv s/s Batala. | 3.95 Lakh | 2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000 | 60 Days |

| | | | | |
|------------|---|-----------|---|---------|
| 45/2023-24 | Repair and Maintenance of sub division office of civil works PSTCL, Ludhiana. | 1.90 Lakh | 2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000 | 45 Days |
| 46/2023-24 | Replacement of submersible pump motor at 220kv s/s Dasuya. | 28,000/- | 2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000 | 30 Days |

General Terms & Conditions:-

1. The Tender documents cost is not charged as per Financial Advisor, PSTCL, Patiala(Budget Section) O/o No: 10 dt: 22-2-18 and Earnest Money need to be paid in the form of cash or Demand Draft drawn on any scheduled bank in the favour of Senior executive engineer, P&M Civil Maintenance Division, PSTCL Jalandhar.
2. Earnest money shall be 2% of tender value with minimum of Rs.5000/- whichever is higher. Earnest money shall be nil for work order below Rs.50,000/- as per Works Regulations. The **Earnest Money along with Documents** should be kept in envelope duly sealed super-scribed "**EARNEST MONEY**" and **Quotation** should be kept in separate envelope duly sealed super-scribed "**QUOTATION**".
3. Quotations not accompanying the EMD as per sr. no. 2 will not be entertained.
4. Tenders for part work, Conditional tenders, telegraphic tender through fax or tenders not on prescribed forms of tenders without earnest money in the required shape shall not be accepted.
5. A set of tender documents (non-transferable) containing technical specifications, general instructions, terms & conditions can be downloaded from www.pstcl.org or obtained from the office of Sr. Xen P&M Divn, PSTCL Jalandhar by dated 28.08.2023 up to 01:00 PM
6. Work shall be carried out as per PWD specifications to meet with the requirements of the work at site to the entire satisfaction of the Engineer-in-Charge.
7. GST is applicable as per Govt. norms.
8. The quoted Rate shall be valid up to 120 days and shall remain firm through to the completion of work
9. If the work is not completed within stipulated period, PSTCL shall impose 0.5% penalty per week subject to the maximum of 5% of the Total amount.
10. Security Deposit: 5% of the Gross Value of the work done will be deducted from the running bills as Security Deposit. No interest shall be payable to contractors on the amount of security deposit.
11. Income Tax, Labour cess shall be deducted at the source as per prevailing rules and rates.
12. All statutory rules and regulations such as EPF regulations, Labour Rules and Regulations, wages regulations etc. shall be followed by the contractor. The contractor will be fully responsible for any kind of penalty levied by Central/ State Govt. or any other agency for not following the statutory rules and regulation.
13. The quotation should accompany PAN Proof, GST Registration proof and a valid registration of the firm with Pb. PWD, MES, PSPCL, and PSTCL etc.
14. Payment for the work done will be made by Sr. XEN, Civil Maintenance Division, PSTCL Jalandhar.
15. The Tenderer should possess the requisite documents before the date of publishing of this Tender.
16. The undersigned reserves the right to cancel the aforesaid tender at any stage without assigning any reason.
17. In case the date of opening of tenders happens to be a holiday, the tenders will be received and opened on the next working day at the same time.
18. The competent authority reserves the right to increase/decrease the scope of work or also reject any or all the tenders so received without assigning any reason whatsoever.

19. Bidders should note that in case of award of contract they shall themselves be responsible for compliance of various provisions of EPF Act 1952 amended up to date as principal employer, GST which ever are applicable. All obligations arising on this account shall be sole responsibility of the contractor.
20. The terms and conditions of **PSEB WORK REGULATIONS 1997 along with Amendments** will be applicable on this Tender.
21. Tenders received after the due date & time, even if posted before the due date of opening shall not be entertained at all.




Sr. XEM / Civil
Civil Mtc Division,
PSTCL, Jalandhar

Endst No. 1537/08

Date 10/08/20

Copy of above is forwarded to the following for information and necessary action

- 1 Dy Chief /Civil, P&M Circle, PSTCL, Jalandhar.
2. Notice Board.


Sr. XEM / Civil
Civil Mtc Division,
PSTCL, Jalandhar 

Punjab State Transmission Corporation Limited

DNIT for Repair of Control Room at 220 KV S/Stn Chohla Sahib under P&M Division Patti.

| S.No | Qty | Description of Item | Unit | CSR Ref | Deptt Rates | Rate to be quoted by contractor |
|------|-------|--|----------|---------|-------------|---------------------------------|
| 1 | 100 | Regrading terracing of mud plaster covered with tiles or bricks in cement by dismantling tiles or bricks, removing mud plaster, preparing the surface of mud plaster to proper, slope, relaying mud plaster Gobri leaping and tiles or bricks grouted in cement mortar 1:3 | Sqm | 31.11 | 348.68 | |
| 2 | 40 | Cement Concrete 1:2:4 gola 10cm x 10cm concave quadrant along junction of roofs with parapet wall finished smooth. | Rmt | 13.55 | 44.4 | |
| 3 | 0.925 | Replacement of Worn out Tiles with New Tiles on Roof (5350+535+53.50)=5938.5 | Nos/thou | M.Rate | 5943.85 | |
| 4 | 100 | Providing and Fixing Polythene Sheet | Sqm | M.Rate | 15 | |
| 5 | 37 | 12.5 mm thick cement plaster 1:4 | Sqm | 15.9 | 136.67 | |
| 6 | 9 | Providing and fixing 110 mm dia . U.P.V.C Rain water pipe of 2.5 kgf./sqm as per IS:4985 | Rmt | 13.74 | 108.93 | |
| 7 | 37 | Scraping Cement plaster | Sqm | 8.31c | 32.14 | |
| 8 | 15 | Dismantling of floor tiles at any floor of the building, laid in cement mortar including dismantling of cement concrete base | Sqm | 30.95 | 96.43 | |
| 9 | 46.2 | Dismantling of wall tiles at any floor of the building, laid in cement mortar including scraping of cement plaster and disposal of malba at a suitable place within a distance of 100 Mtrs of the complex complete in all respect. | Sqm | 30.94 | 92.86 | |
| 11 | 15 | Providing and laying Anti skid Ceramic floor tiles of size 300x300 mm x 10 mm thick of 1st quality make in colours such as White, Ivory, Grey, Fume Red Brown, laid on flooring skirting and dado in 12.5mm thick cement plaster 1:3 | Sqm | 14.72 | 557.22 | |
| 12 | 46.2 | Providing and fixing 1st quality ceramic glazed wall tiles of size 200 x 300 mm, 100x200mm, 200x200mm in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:4 | Sqm | 14.125 | 592.08 | |
| 13 | 42 | Providing and laying vitrified floor tiles of different sizes in light colour shades made using Double Charge technology in all colours and shades, laid on 20mm thick cement mortar 1:4, complete.Size 600x600 mm | Sqm | 14.113 | 887.58 | |
| 14 | 42 | Dismantling cement conglomerate floors 25mm to 50mm thick including concrete base. | Sqm | 8.16 | 97.32 | |
| 15 | 42 | Conglomerate floor 25mm thick cement concrete topping 1:2:4 using mechanical mixer for mixing of material | Sqm | 14.5 | 169.72 | |

| | | | | | | |
|----|-------|---|------|----------|---------|--|
| 16 | | Providing and fixing aluminum work for doors, windows, ventilators and partitlons with extruded built up standard tubular sections/appropriate z sections of Jindal, Hindalco, Mahavir or equivalent make | Kg | 17.45A | 314.29 | |
| | 42.35 | For fixed portion and chawkhats | | | | |
| 18 | 30.87 | For shutters of doors windows & ventilators including providing and fixing hinges/pivots and making provisions for fixing of fittings where ever required including the cost of PVC/neoprene gaskets as required | Kg | 17.45B | 328.57 | |
| 19 | 1.69 | Providing and fixing 12mm thick prelamated particle board flat pressed three layer or graded wood particle board in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete | Sqm | 17.46ii | 1025 | |
| 20 | 1.35 | Providing and fixing glazing in aluminum door, window, ventilator shutters and partitons etc. Float glass panes of 5 mm thickness | Sqm | 17.47i | 924.11 | |
| 21 | 10 | Cost of aluminum fittings complete for doors, windows such as tower bolts, handles, Stoppers and screw etc. for these fittings For shutter area above 0.50 sqm | Sqm | 17.23ii | 99.11 | |
| 22 | 2 | Providing and fixing in position Chinaware European type water closet P trap or S trap suite-consisting of 10 ltr. PVC flushing cistern supported on angle iron bracket, short bend 32 mm dia | each | 30.4 | 4267.86 | |
| 23 | 2 | Providing and fixing jet spray with 2'-6" long PVC pipe. With C.P. Brass nut | each | 30.8a | 425 | |
| 24 | 2 | Providing and fixing in position best Indian make white ordinary lavatory suites consisting of C.P. brass waste 32mm dia, pair of angle iron bracket with one C.P. brass tap complete. Size 550 mm x 400 mm x 830mm | each | 30.32ii | 3226.79 | |
| 25 | 2 | Providing & fixing in position vitreous Chinware white Indian make flat back or angular lipped front small urinals size 265x315x440mm approved make with C.P. brass tube connection 300 mm long | each | 30.15 | 2666.96 | |
| 26 | 2 | Providing & Fixing in postion 15 mm i/d bib cock of cp brass without flange. (ii) C.P. brass Bib cock foam flow without flange | each | 30.65aii | 818.75 | |
| 27 | 2 | Providing & Fixing in position 5mm thick bevelled edge mirror of superior glass complete with 4mm thick hard board backing fixed in with rawl plugs 50mm, C.P. brass screws and washers and S/S Studs on top (a) Size 600mmx450mm | each | 30.61a | 1070.54 | |
| 28 | 6 | Providing & Fixing in postion stop cock / Angle valve of approved make complete in all respect. (c) C.P. brass 15mm Angle valve without flange | each | 30.66c | 737.5 | |
| 29 | 6 | Providing & fixing in position PVC flexible tube connection of size 15 mm x 300 mm with C.P. Brass nut | each | 30.72a | 155.36 | |
| 30 | 6 | Providing and fixing in position SS Grating with frame of approved make | each | 30.8 | 98.8 | |

| | | | | | | |
|----|------|--|-----|----------|--------|--|
| 31 | 40 | Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes U V stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply including all PP-R plain & brass threaded 20mm o/d | Rmt | 29.39A b | 135.48 | |
| 32 | 3.82 | Extra Carriage of Fine Sand | Cum | Annex | 256.8 | |
| 33 | 1.6 | Extra Carriage of Cement | MT | Annex | 431.85 | |
| 34 | 0.61 | Difference of Material for Crusher 13.2mm | Cum | Annex | 329.7 | |
| 35 | 0.61 | Difference of Material for Crusher 11.2mm | Cum | Annex | 361.36 | |
| 35 | 3.7 | Difference of Material for Tiles | Cum | Annex | 653.38 | |

Notes: -

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowl store as per availability.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS Items is given.
3. For any NS Item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – In – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor