PSTCL
PUNJAB STATE TRANSMISSION CORPORATION LIMITED

PUNJAB STATE TRANSMISSION CORPORATION LIMITED
O/o Sr.XEN , Grid Const Division
PSTCL, Shakti Sadan Jalandhar.
Phone/Fax: 0181-2225785

Memo No.

Dated _____

Enquiry No. 04 / 2018-19

Dated 16-4-2018

REGISTERED
To

1. M/S VEE KAY Electricals , Kartar Nagar , Chheharta (Amritsar).
2. M/S EHVEE ENGINEERS, Opp. Jaslon Building, Batala Road Amritsar.
3. M/S RAJINDERA ASSOCIATES 33 GARDEN COLONY , AMRITSAR.
4. M/S Choudary Electrical Enterprises , Gali Sham sunder Jyotshi New Railway road .
5. M/S S.G.S Contractor , EE-52 , Bagh Karam Bakash , Jalandhar

Sub: **EXECUTION OF JOB**

Dear Sir,

Your sealed quotations are invited for the execution of following jobs at 220 KV S/S Verpal as detailed below. Quotation, duly completed in all respect should reach in this office on or before dated 2-5-2018 up to 10:00 am. These quotations will be opened on dated 2-5-2018 at 11:00 am in the presence of the Contractors/suppliers or their representative, who may like to be present. If this day happens to be a holiday, the same will be opened on the next working day at the same time.

Sr. No.	Description of Work	Units	Qty.
1	Unloading of 100 MVA 66/11 KV Power T/F from trailor to plinth. The work includes unloading of T/F body from trailor to wooden sleeper plinth adjacent to the old plinth. After unloading of old plinth to new plinth by civil wing , the T/F body will be dragged on rails upto rail cum road track and then fixing o wheels. The changing the direction of wheels and dragging the T/F to its position at plinth. The special T&P like (wooden sleeper T/F to its pilling arrangements and rails etc) required for the work will be provided by the department .	No	01

Terms and conditions:

1. The rates should be quoted FOR destination and valid for a minimum period of 30 days.
2. The undersigned reserve the right to cancel any or all the quotations without assigning any reason.
3. Conditional/telegraphic quotations shall not be accepted.
4. The quantity can be increased or decreased at the time of placing of W.O
5. The work shall be completed as per standard drawing and design of PSTCL
6. The work shall be completed within 30 days of issue of work order
7. No material shall be allowed to be removed out of the yard
8. The work shall be completed to the satisfaction of Engineer In charge of the work.
9. Material for above Panels will be supplied/Dismentaled by department.
10. The 2% earnest money of the estimated cost or Rs. 5000- whichever is higher, should be accompanied with The quotation in a separate envelope. The estimated cost as per Labour Schedule rates are Rs. 1,10,000 - and GST Extra (as applicable) .

Sr.XEN ,
Grid Const. Division,
PSTCL, Shakti Sadan, Jalandhar

Endst.No. 1292/95 Dated 16-4-2018

Copy of the above is forwarded to the following for information and further necessary action please.

1. Dy. C.E , Grid Construction, Circle PSTCL,Ludhiana.
2. A.E.E. Grid Sub division , PSTCL. Amritsar.
3. Sr.XEN / IT PSTCL , Patiala for uploading on PSTCL Website.
4. Notice Board

The Amount will be charged to 100 MVA 220/66 KV Power T/F at 220 KV S/S Verpal

Sr. XEN ,
Grid Const. Division,
PSTCL Shakti Sadan, Jalandhar