PUNJAB STATE TRANSMISSION CORPORATION LIMITED
O/o Sr.XEN , Grid Substation Division
PSTCL, Shakti Sadan Jalandhar.
Phone/Fax: 0181-2225785

Memo No. 1615 Dated 11/6/19

Enquiry No.07/2019-20 **Dated** 11/6/19

REGISTERED

To

1. M/S VEE KAY Electricals , Kartar Nagar , Chheharta (Amritsar).
2. M/S EHVEE ENGINEERS, Opp. Jasion Building, Batala Road Amritsar.
3. M/S RAJINDERA ASSOCIATES 33 GARDEN COLONY , AMRITSAR.
4. M/S Choudary Electrical Enterprises , Gali Sham sunder Jyotshi New Railway road.
5. M/S S.G.S Contractor , EE-52 , Bagh Karam Bakash , Jalandhar

Sub: **EXECUTION OF JOB**

Dear Sir,

Your sealed quotations are invited for the execution of following jobs at 220 KV S/S Dhilawan as detailed below. Quotation, duly completed in all respect should reach in this office on or before dated 26-6-19... up to 02:00 pm. These quotations will be opened on dated 26-6-19... at 03:00 pm in the presence of the Contractors/suppliers or their representative, who may like to be present. If this day happens to be a holiday, the same will be opened on the next working day at the same time.

Sr. No.	Description of Work	Units	Qty.
1	Erection of 220 Volt 200 AH battery set for 2nd dc source at 132 KV S/S Dhilwan. The work includes unpacking of material (including battery charger, DCDB, 200 AH 220 Volt battery set, stand, Electrolyte cans etc) and shifting of material inside battery room. Then assembly of battery stand, mounting of all the 110 No. battery cells on the stnd (ensure placing insulators below the cells), pouring of electrolyte into all the battery cells and then making connectioins of the cells. The work also includes laying of AC, DC cables from battery to battery charger and DCDB and DCDB to different panels installed in the control room, completing 03 No. charging-discharging cycles, then compelte the work by commissioning of the battery set. The work also includes earthing of DCDB and battery charger with MS flat. The material required for the work will be supplied by the department.	No.	01

Terms and conditions:

1 The rates should be quoted FOR destination and valid for a minimum period of 60 days.
2 The undersigned reserve the right to cancel any or all the quotations without assigning any reason.
3 Conditional/telegraphic quotations shall not be accepted.
4 The quantity can be increased or decreased at the time of placing of W.O
5 The work shall be completed as per standard drawing and design of PSTCL
6. The work shall be completed within 60 days of issue of work order
7. No material shall be allowed to be removed out of the yard
8. The work shall be completed to the satisfaction of Engineer In charge of the work.
9. Material for above towers /beams will be supplied by department.
10 The 2% earnest money of the estimated cost or Rs. 5000- whichever is higher, should be accompanied with The quotation in a separate envelope . The estimated cost as per Labour Schedule rates are Rs. 37,000 and GST Extra (as applicable) .

Sr.XEN ,
Grid Const. Division,
PSTCL, Shakti Sadan, Jalandhar

Endst.No. 1615 Dated 11/6/19

Copy of the above is forwarded to the following for information and further necessary action please.

1 Dy. C.E , Grid Construction, Circle PSTCL,Ludhiana.
2 A.E.E, Grid Const Sub division , PSTCL, Amritsar.
3 Sr.XEN/IT PSTCL , Patiala for uploading on PSTCL , website.
4 Notice Board .

The Amount will be charged to Prov Addl. 220 Volt AH 2nd DC Source Battery Set at 132 KV S/S Dhilwan.

Sr.XEN ,
Grid Const. Division,

Scanned by CamScanner