PUNJAB STATE TRANSMISSION CORPORATION LIMITED
O/o Sr.XEN , Grid Substation Division
PSTCL, Shakti Sadan Jalandhar.
Phone/Fax: 0181-2225785

Memo No.
Enquiry No. 14/ **2019-20**

Dated _____
Dated 29-7-19

REGISTERED
To

1) M/S EHVEE Engineers, EE-52 Bhag shivraj garh Jalandhar.
2) M/S C.S.C Contractor , 75 New Raja Gardan extn. Mithapur Road Jalandhar.
3) M/S ARR CEE EK-319 , Pipal gali shivraj garh Jalandhar
4) M/S S.G.S Contractor EE-52 Bhag karam Bakash , Jalandhar
5) M/S RAJINDERA Associates 33 Garden Colony, Amritsar.

Sub: **EXECUTION OF JOB**

Dear Sir,

Your sealed quotations are invited for the execution of following jobs at 220 KV S/S Dasuya as detailed below. Quotation, duly completed in all respect should reach in this office on or before dated 13-8-19 up to 09:30 pm. These quotations will be opened on dated ~~29-7-19~~ 13-8-19 at 10:00 pm in the presence of the Contractors/suppliers or their representative, who may like to be present. If this day happens to be a holiday, the same will be opened on the next working day at the same time.

Sr. No.	Description of Work	Units	Qty.
1	220 ਕੇ.ਵੀ ਸਬ ਸਟੇਸ਼ਨ ਦਸੂਹਾ ਵਿਖੇ ਟ/ਫ ਨੂੰ ਸਲੀਪਰ ਰੇਲਾਂ ਤੇ ਖਿੱਚਣ ਲਈ ਅੰਦਰ ਦਬੱਨ ਵਾਸਤੇ 10 ਫੁੱਟ ਲੰਬਾ 03 ਫੁੱਟ ਚੋੜਾ ਤੇ 10 ਫੁੱਟ ਡੂੰਘਾ ਖੱਡਾ ਪੱਟਣਾ, ਖੱਡੇ ਵਿੱਚ 10 ਫੁੱਟ ਲੰਬੀ ਰੇਲ ਅਤੇ ਸਲੀਪਰ ਸਮੇਤ ਰੈਪ, ਸ਼ਲਿੰਗ ਪਾਉਣਾ ਅਤੇ ਖੱਡੇ ਨੂੰ ਮਿੱਟੀ ਨਾਲ ਪੂਰਨਾ, ਖਿਚਾਈ ਹੋਣ ਤੋਂ ਬਾਅਦ ਖੱਡੇ ਨੂੰ ਫਿਰ ਪੁਟਣਾ ਅਤੇ ਬਾਹਰ ਕੱਡਣਾ @ 16000 each.	Nos	02
2	Repair of 100 Ton Hydraulic jack and change its oil seals.	Nos	02
3	Laying of copper control cable of different sizes for 02 Nos 220 kv isolator 03 Nos 220 kv CT's, 01 No 220 kv SF-6 breaker from yard to 220 kv line C&R Panel in the control room as per standard design of PSTCL for newly erected looping in 01 No Addl. 100 MVA power T/F bay at 220 kv s/s Dasuya.	Job	01
4	Laying of copper control cable of different sizes for 01 Nos 66 kv isolator 03 Nos 66 kv CT's and 01 No 66 kv SF-6 breaker from yard to 66 kv line C&R Panel in the control room as per standard design of PSTCL for newly erected looping in 01 No Addl. 100 MVA power T/F bay at 220 kv s/s Dasuya.	Job	01
5	Fabrication of Z type riser of MS Flat size 50x6 mm welding from earth mesh at GI structure for 220/66 KV equipment. Welding edge with the structure should be 4". The work including digging of earth up to mesh level then jointing the MS Flat with mesh and GI structure by welding will covered with bitumen compound. The work includes all works associated with Z type riser as per site requirements.	Nos	50
6	Laying of Cu control cables for 100 mva 220/66 KV power t/f, marshalling box, OLTC, Fans, Buchhloz etc installed at 220 kv S/S Dasuya yard, the work also including laying of different size of copper control cables from T/f yard to C&R pannel in the control room as per standard design of PSTCL as per site requirement at 220 kv s/s Dasuya.	Job	01
7	Washing the 100 mva 220/66 kv t/f installed at 220 kv s/s Dasuya and its accessories with Caustic Soda solution for removal of dirt dust sledge and painting the surface and then painting the t/f with lead mixed paint of ISI mark quality paint in 2 coats to finish.	Job	01
8	Scratching of Earthing riser & supporting MS Flats, MS angles and MS Channels with sand paper then one coat of red oxde metallic paint and complete it with black paint at supporting flats, angles and channels, green at earthing riser and phase sequence with RYB identification painting for 01 Nos 220 KV bay 01 No. 220 T/F bay, 01 No. 66 KV T/F bay and switchgear yard at 220 KV S/S Dasuya.	Job	01
9	Complete in double earthing to 100 MVA 220/66 KV Power T/F including fans Cooling bank main marshalling box.	Job	01
10	Fabrication Supply of following size wooden gutka. 1. 18" X 10" X 8". 2. 18" X 10" X 5". 3. 18" X 10" X 3".	Nos Nos Nos	06 10 07
11	Shifting and loading of 40K ltrs. Capacity tank from site and unloading the same with crane at 220 KV S/S Dasuya.	Job	01
12	220 ਕੇ.ਵੀ ਸਬ ਸਟੇਸ਼ਨ ਦਸੂਹਾ ਵਿਖੇ 100 ਐਮ.ਵੀ.ਏ ਟ/ਫ ਦੇ ਤੇਲ ਤੇ ਭਰੇ ਡਰਮਾਂ ਨੂੰ ਯਾਰਡ ਤੋਂ ਟ/ਫ ਦੇ ਨੇੜੇ ਲਿਖਾ ਕੇ ਖੜੇ ਕਰਨੇ ਅਤੇ ਫਿਲਟਰ ਸੈਟ ਨੂੰ 3.5 ਕੈਰ ਕੇਬਲ ਵਿਛਾ ਕੇ ਏ.ਸੀ ਸਪਲਾਈ ਮੁਹਇਆ ਕਰਵਾਕੇ ਸੈਟ ਚਾੱਲੂ ਕਰਨਾ।	Job	01
13	100 MVA 220/66 ਪਾਵਰ ਟ/ਫ ਨੂੰ ਫਿਲਟਰ ਸੈਟ ਤੋਂ ਤੇਲ ਫਿਲਟਰ ਕਰਨ ਲਈ ਵੱਖ ਵੱਖ ਕਿਸਮ ਦੇ ਫਲੈਂਜਿਜ ਸਮੇਤ ਗੈਸ ਕਿੱਟਾ ਤਿਆਰ ਕਰਨ ਸਬੰਧੀ।	Job	01

Terms and conditions:

1 The rates should be quoted FOR destination and valid for a minimum period of 60 days.
2 The undersigned reserve the right to cancel any or all the quotations without assigning any reason.
3 Conditional/telegraphic quotations shall not be accepted.
4 The quantity can be increased or decreased at the time of placing of W.O
5 The work shall be completed as per standard drawing and design of PSTCL

Scanned by CamScanner