PUNJAB STATE TRANSMISSION CORPORATION LIMITED

O/o Sr.XEN , Grid Substation Division
PSTCL, Shakti Sadan Jalandhar.
Phone/Fax: 0181-2225785

Memo No. 891/95 Dated 4/3/2020

Enquiry No. 66/2019-20 Dated 4/3/2020

REGISTERED
To

1) M/S EHVEE Engineers, Opp. Jaslon Buliding, Batala Road Amritsar.
2) M/S CSC Contractor, 75 New Raja Garden Extn. Mithapur Road, jalandhar.
3) M/S ARR CEE EK-319, Pipal gali Shivraj garh jalandhar.
4) M/S S.G.S Contractor EE-52 Bhag Karam Bakash , jalandhar.
5) M/S RAJINDERA Associates 33 Gardan Colony, Amritsar..

Sub: **EXECUTION OF JOB**

Dear Sir,

Your sealed quotations are invited for the execution of following jobs at 132 KV S/S Tanda as detailed below. Quotation, duly completed in all respect should reach in this office on or before dated 13/3/2020 up to 09:30 am. These quotations will be opened on dated 13/3/2020 at 10:00 am in the presence of the Contractors/suppliers or their representative, who may like to be present. If this day happens to be a holiday, the same will be opened on the next working day at the same time.

Sr. No.	Description of Work	Units	Qty.
1	Erection of 220 Volt 200 AH Battery Set for 2nd DC source at 132 kv s/s Tanda. The work includes unpacking for material (including battery charger, DCDB, 200 AH 220 volt battery set, stand, electrolyte can etc.) and shifting of material inside battery room. The assembly of battery stand , mounting of all the 110 no. battery cells on the stand (ensure placing insulators below the cells), pouring of electrolyte into all the battery cells and then making connections of the cells. The work also includes laying of AC, DC cables from battery to battery charger and DCDB and DCDB to different panels installed in the control room, completing 3 no. charging –discharging cycles, then complete the work by commissioning of the battery set. The work also includes earthing of DCDB and battery charger with MS flat. The material required for the work will be supplied by the department.	Job	1

Terms and conditions:

1 The rates should be quoted FOR destination and valid for a minimum period of 30 days.
2 The undersigned reserve the right to cancel any or all the quotations without assigning any reason.
3 Conditional/telegraphic quotations shall not be accepted.
4 The quantity can be increased or decreased at the time of placing of W.O
5 The work shall be completed as per standard drawing and design of PSTCL
6. The work shall be completed within 60 days of issue of work order
7. No material shall be allowed to be removed out of the yard
8. The work shall be completed to the satisfaction of Engineer In charge of the work.

Sr.XEN ,
Grid Const. Division,
PSTCL, Shakti Sadan, Jalandhar

Endst.No. 896/99 Dated 4/3/2020

Copy of the above is forwarded to the following for information and further necessary action please.

1 Dy. C.E , Grid Construction, Circle PSTCL,Ludhiana.
2 A.E.E, Grid Const Sub division PSTCL, Jalandhar.
3 Sr.XEN/IT PSTCL , Patiala for uploading on PSTCL , website.
4 Notice Board .

The Amount will be charged to Erection of 220 kv Volt 200 AH Battery set for 2nd DC Source at 132 kv s/s Tanda

Sr.XEN ,
Grid Const. Division,
PSTCL Shakti Sadan, Jalandhar.

Scanned with CamScanner