

DNIT for Repair Of Damaged U Fencing and Boundry wall at 132 kv s/s Kangra

S No	Description of an item	Qty	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	Earthwork In Excavation in all kind of soil	13.97	Cum	6.6	162.50	
2	PCC 1:6:12 with 40 mm stone aggregate	4.73	Cum	10.7(b)(ii)	2309.18	
2	Dismantling of concrete for Removal of Old Angle	1.27	Cum	8.6 (d)	1218.75	
3	PF/ Angle iron post 75x75x8 3.12 mtr @4.50kg/Rm	222.14	kg	NS	63	
4	P/F Angle iron post 50x50x6 mm 3.12 mtr. Long @4.50kg/Rm	421.20	kg	NS	63	
5	P/F Angle iron post 50x50x6 mm 2.60 mtr. Long @4.50kg/Rm	93.60	kg	NS	63	
6	First class brick work in cement sand mortar 1:5 above plinth level	11.79	Cum	11.6	4088.20	
7	Centring and shuttering of block for grouting of Angle Iron	16.20	Sqm	9.8	475.00	
8	Cement concrete 1:2:4 for grouting of Angles as per CSR 10.13	0.95	Cum	10.13(i)	2331.73	
9	12.5 MM thick cement plaster 1:5 OLD Toe Wall	154.80	sqm	15.10	136.48	
10	Priming coat over mettalic surface including preperaton of surface with special quality paint	25.70	Sqm	16.20	21.43	
11	Scraping of Old Paint form Angles for new one	27.18	Sqm	16.36	90.18	
12	Painting two coats with aluminium paint of special quality	52.88	Sqm	16.25 (a)	56.25	
13	P/F wire netting mesh of G.I. ,12 Gauge 50x50 Mesh 180 cm high complete as per NS Item	180.00	Rmt	NS	441.92	
14	P/F Barbed wire 4 rows over angle for U-Fencing complete AS per NS item	180.00	Rmt	NS	93.36	
15	Clearing jungle manually including uprooting rank vegetation, grass, woody vegetation up to 30 cm girth measured at height of 1 m above	360.00	Sqm	32.4 C	7.11	
16	Extra Carriage and difference of material for coarse sand	0.43	Cum	AOR	355.93	
17	Extra Carriage for fine sand	7.77	Cum	AOR	256.80	
18	Extra Carriage and difference of material for Crusher 13. 2mm	0.43	Cum	AOR	203.50	
19	Extra Carriage and difference of material for Crusher 11. 2mm	0.43	Cum	AOR	184.29	
20	Extra Carriage and difference of material for Stone metal	4.68	cum	AOR	177.46	
21	Diff of material rates for bricks	5.659	1000 nos	Annexure	587.24	

22	recover of scrap	100.00	kg	Annexure	20.00	
23	Extra carriage for Cement	2.45	MT	Annexure	599.78	

Notes: -

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowal store(As per Availability).
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.

5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

6. At the time of final billing, the merit position w.r.t actual work done shall be prepared again and total payment to be paid to the contractor shall be restricted as per cost percentage w.r.t. departmental rates of L-1 in revised comparative statement and approved comparative statement . In case if the merit position of L-1 contractor changes, the total payment to contractor will be restricted to L-1 Cost of revised comparative statement.

Signature of vendor