S No	Description of an item	Qty	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	Dismantling of concrete for Removal of Old Angle	0.56	Cum	8.6 (d)	1218.75	
2	P/F Angle iron post 50x50x6 mm1.20 mtr. Long @4.50kg/Rm	97.20	kg	NS	63	
3	PF/ Angle iron post 75x75x8 3.12 mtr @4.50kg/Rm	55.54	kg	NS	63	
4	P/F Angle iron post 50x50x6 mm 3.12 mtr. Long @4.50kg/Rm	140.40	kg	NS	63	
5	P/F Angle iron post 50x50x6 mm 2.60 mtr. Long @4.50kg/Rm	46.80	kg	NS	63	
6	Dismantling of brick work in cement	5.22	Cum	8.5(b)	608.93	
7	Scraping of bricks Dismantled from brick work	1.002	1000nos	8.31(e)	1410.71	
8	PCC 1:6:12 with 40 mm stone aggregate Boundary wall	5.76	Cum	10.8(b)(ii)	2309.18	
9	First class brick work in cement sand mortar 1:7 in foundation and plinth.	20.02	cum	11.1(i)	4095.13	
10	First class brick work in cement sand mortar 1:5 above plinth level	29.70	Cum	11.5	4088.20	
11	Centring and shuttering of block for grouting of Angle Iron	9.72	Sqm	9.8	475.00	
12	Cement concrete 1:2:4 for grouting of Angles as per CSR 10.13	1.00	Cum	10.13(i)	2331.73	
13	12.5 MM thick cement plaster 1:5 OLD Toe Wall	270.65	sqm	15.10	136.48	
14	Priming coat over mettalic surface including preperaton of surface with special quality paint	8.78	Sqm	16.20	21.43	
15	Scraping of Old Paint form Angles for new one	43.37	Sqm	16.36	90.18	
16	Painting two coats with aluminium paint of special quality	52.15	Sqm	16.25 (a)	56.25	
17	P/F wire netting mesh of G.I. ,12 Gauge 50x50 Mesh 180 cm high complete as per NS Item	160.00	Rmt	NS	441.92	
18	P/F Barbed wire 4 rows over angle for U-Fencing complete AS per NS item	210.00	Rmt	NS	93.36	

19	Clearing jungle manually including uprooting rank vegetation, grass, woody vegetation up to 30 cm	320.00	Sqm	32.4 C	7.11	
20	Extra Carriage and difference of material for coarse sand	0.45	Cum	Annexure	346.54	
21	Extra Carriage for fine sand	19.62	Cum	Annexure	256.80	
22	Extra Carriage and difference of material for Crusher 13. 2mm	0.45	Cum	Annexure	128.04	
23	Extra Carriage and difference of material for Crusher 11. 2mm	0.45	Cum	Annexure	210.58	
24	Extra Carriage and difference of material for Stone metal	5.70	cum	Annexure	133.00	
25	Diff of material rates for bricks	22.863	1000 nos	Annexure	587.24	
26	recovery of bricks (5100+10%+1%)	1.002	nos	Annexure	-5666.10	
27	recover of scrap	220.00	kg	Annexure	-20.00	
28	Extra carriage for Cement	5.45	MT	Annexure	439.56	

Notes: -

- These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowal store(As per Availability).
- PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
- 3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er in Charge.
- 4. GST will be applicable as per Govt. norms and will be paid extra.
- Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.
 - At the time of final billing, the merit position w.r.t actual work done shall be prepared again and total payment to be paid to the contractor shall be restricted as per cost percentage w.r.t. departmental rates of L-1 in revised comparative statement and approved comparative
- statement . In case if the merit position of L-1 contractor changes, the total payment to contractor will be restricted to L-1 Cost of revised comparative statement.

Signature of vendor