

**DNIT for Repair and maintenance of CE/P&M Office building Ludhiana**

S No	Qty	Description of an item	Units	CSR Ref	Department Rates	Rate to be quoted by contractor
1	45.24	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade (two coats)	sqm	16.63	79.46	
2	11.31	Preparation of plastered or concrete surface for painting (including sand papering the surface) using ready mixed cement based wall putty by applying two coats to get required finish	sqm	16.65	71.43	
3	90.24	Finishing walls with acrylic smooth exterior paint of required shade with two coats applied @ 1.67 litre/10sqm over and including base coat of water proofing Cement Paint applied @ 2.20 Kg/10 sqm	sqm	16.59	107.14	
4	810	Painting new letters and figures of black synthetic enamel paint to an even shade	cm ht per letter	16.47	2.36	
5	2	Providing and fixing hydraulic door closer ISI mark with necessary screw etc. complete I.S.I Designation No. III (size of door 851mm to 1000mm)	Each	17.43 c	1169.64	
6	2	Providing & Fixing in position 15 mm i/d bib cock of cp braas without flange (as approved by the Engineer-in-charge).	No.	30.65 a ii	818.75	
7	2	Providing & Fixing in position stop cock/angle valve cp brass (as approved by the Engineer-in-charge).CP Brass 15mm stop cock male and female end	No.	30.66(a)	716.96	
8	4	P&F In position PVC flexible tube connection of approved make PVC tube connection of size 15 mm X 450 mm with CP Brass nut	No.	30.72 b	162.5	
9	1.215	Steel work fixed independetlty without connecting plates including cutting hoisting and fixing position © Tees angles & channels	Qtl	18.1 c	5294.64	
10	10.8	Painting two or more coats with synthetic enamel paint in all shades on old wood work or metallic or plastered or concrete surfaces to give an even shade including rubbing down old paint.	sqm	16.18	57.14	
11	15	P&F commercial plywood 18 mm thick	sqm	17.51	1115.18	
12	15	P&F decorative lamiated sheet 0.72 mm thick and reverse side of adhesive bonding icluding cost of adhesive of approved quality	sqm	17.93	739.29	
13	13.8	Providing precast cement concrete jali 1:2:4 reinforced with 1.6 mm dia mild steel wiring including centering shuttering cleaning and fixing and finishing I cement mortar 1:3 25 mm thick	sqm	10.51 C	974.11	

14	48	Site clearance Excavation in dumped stone or malba including stacking of unserviceable material separately and disposal of unserviceable material. Lead up to 50 m and lift up to 1.5 m, disposed material to be neatly dressed in all kinds of soils.	cum	32.4 A	296.43	
15	612	Site clearance Clearing jungle manually including uprooting rank vegetation, grass, woodyvegetation up to 30 cm girth measured at height of 1 m above ground level and removal of rubbish up to distance of 50 m outside the periphery of the area cleared	sqm	32.4 C	7.11	
16	1	Hydraulic Excavator of 1 cum bucket (60 cum/hour)	hour	2.32	1177.5	
17	12.5	Providing, Laying , fixing & jointing of P.V.C. Pipes as per ISI-4985 (ISI marked with the prior approval of Engineer-in-Charge) along the Trenches and laying the same in Trenches 110mm o/d pipe of 6 Kgf. / sqcm	Rmt	28.13 xv	375.25	
18	500	Providing & fixing in position on terrace (at all floor levels) HDPE tank cover for water storage tanks of approved make (to the approval of Engineer -in-charge) complete in all respect. Triple layer tank	Ltrs	30.97 A(i)	9.64	

**Notes: -**

1. These rates are through rates exclusive of Cement & Steel.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.

Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

At the time of final billing, the merit position w.r.t actual work done shall be prepared again and total payment to be paid to the contractor shall be restricted as per cost percentage w.r.t. departmental rates of L-1 in revised comparative statement and approved comparative statement . In case if the merit position of L-1 contractor changes, the total payment to contractor will be restricted to L-1 Cost of revised comparative statement.

**Signature of vendor**