

DNIT for Repair & Maintenance Of Road In front of ODTL Lab, Ludhiana						
S No	Qty	Description of an item	Units	CSR Ref	Deptt. Rates	Rate to be quoted by contractor
1	451.50	Scarifying Existing Bituminous Surface to a depth of 50mm by Mechanical Means.Scarifying the existing Bituminous road surface to a depth of 50mm and disposal of scarified material with in all lifts and lead upto 1000 meters	sqm	24.3 b	4.46	
2	67.73	Earth work undressed with a combined lead upto 15 meters including breaking of clouds	cum	6.2 b	97.32	
3	45.15	Cement Concrete 1:5:10 With stone aggregate 40mm gauge mixing by mechanical means using concrete mixer	cum	10.9 b ii	2305.82	
4	45.15	Reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixer as per IS:1791 and vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in foundation and plinth.	cum	10.15	2809.51	
5	39.00	Shuttering for faces of concrete foundations and foundation beam & plinth beam (vertical or battering)	sqm	9.1	187.5	
6	12.03	Cold twisted detormed (Ribbed/ Tor steel) Bars (Fe 500 grade as per IS 1786-2008) , for R.C.C works, where not including in the complete rate of RCC including bending and binding placing in position complete	Qtl	18.18	780.36	
7	350.00	Joint Sealing Compound. Providing and filling joint sealing compound with coarse sand and 6 percent bitumen by weight complete as per drawings and technical clause 2605 of MORT&H specifications	Metre per cm depth	2.84	2.54	
8		Extra carriage and difference of material rates.				
(i)	21.45	Extra carriage for cement	MT	Annex	352.18	
(ii)	22.12	Extra carriage for fine sand	cum	Annex	256.8	
(iii)	19.41	Extra carriage for coarse sand	cum	Annex	342.68	
(iv)	19.19	Extra carriage for crusher 11.2mm	cum	Annex	377.16	
(v)	19.19	Extra carriage for crusher 13.2mm	cum	Annex	331.14	
(vi)	44.25	Extra carriage for stone metal 40 mm	cum	Annex	336.09	
(vii)	1.2	Extra carriage for steel	MT	Annex	254.23	

Notes: -

- 1 These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowal store(As per Availability).
- 2 PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
- 3 Any error regarding description,reference to CSR,Quantity,rate,premium,unit,calculations omission,addition will be corrected at any stage as per CSR,AOR,Specification and drawings and no claim whatsoever shall be entertained on this account.
- 4 For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
- 5 GST will be applicable as per Govt. norms and will be paid extra.

- 6 Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.
- 7 At the time of final billing, the merit position w.r.t actual work done shall be prepared again and total payment to be paid to the contractor shall be restricted as per cost percentage w.r.t. departmental rates of L-1 in revised comparative statement and approved comparative statement . In case if the merit position of L-1 contractor changes, the total payment to contractor will be restricted to L-1 Cost of revised comparative statement.

Signature of vendor