

DNIT for Protection of tower no. 17, 29 & 72 of 220 KV Moga-Sadiq & 220 KV Moga Bajakhana Transmission line Under TL S/D Makhu (TE-48/2024-25)

Sr No	Qty	Description of work	Unit	CSR Ref	CSR/Dep tt rate	Rate to be quoted by contractor
1	10	Stub strengthening of rusted tower legs, dismantling and remaking the Concrete stub size 450 mm x 450 mm x 1000 mm without offchutes	each	AOR	9577.00	
2	14	Repair and raising of single offchute including welding of rusted/damaged angle iron offchutes of size 230 mm x 230 mm x 1250 mm	each	AOR	4119.00	

Notes: -

- 1 These rates are through rates inclusive of Cement & Steel.
- 2 Any error regarding description,reference to CSR,Quantity,rate,premium,unit,calculations omission,addition will be corrected at any stage as per CSR,AOR,Specification and drawings and no claim whatsoever shall be entertained on this account.
- 3 PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
- 4 For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
- 5 GST will be applicable as per Govt. norms and will be paid extra.
- 6 Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.
- 7 At the time of final billing, the merit position w.r.t actual work done shall be prepared again and total payment to be paid to the contractor shall be restricted as per cost percentage w.r.t. departmental rates of L-1 in revised comparative statement and approved comparative statement . In case if the merit position of L-1 contractor changes, the total payment to contractor will be restricted to L-1 Cost of revised comparative statement.

Signature of vendor