

DNIT for Replacement of existing plinths at 220 KV S/S Ladhawal

S No	Qty	Description of an item	Unit	CSR Ref	CSR/Dept Rates	Rate to be quoted by contractor
1	181.1	Earth work in excavation in foundations trenches etc. in all kinds of soil where Pick-Jumper work is not involved and not exceeding 2.0 metres depth including dressing of bottom and sides of trenches, stacking the excavated soil clear from the edge of excavation and subsequent filling around masonry in 15 cm, layers with compaction including disposal of all surplus soil as directed within lead of 30 metres.	cum	6.6	162.5	
2	5.49	PCC 1:6:12 with 40 mm stone aggregate mixing by mechanical means using concrete mixer volumetric type	cum	10.7 b ii	2309.18	
3	24.39	Cold Twisted deformed bars FE 500 for RCC work including cutting, bending and placing in position in complete	Qtl	18.18	780.36	
4	21	Shuttering for faces of concrete foundations and foundation beam & plinth beam (vertical or battering)	Sqm	9.1	187.5	
5	100.1	Centering and shuttering for flat surfaces such as suspended floors, roofs, landings, chajjas, shelves etc.	Sqm	9.4	425.89	
6	40.66	Reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixer as per IS:1791 and vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in foundation and plinth.	cum	10.15	2809.51	
7	7	Fixing of template	No	NS	200	
8	2.07	First class burnt brickwork laid in cement sand mortar 1:5 in foundation and plinth	cum	11.5	4088.2	
9	9	20 mm thick cement plaster in 1:5 in two coats	Sqm	15.21	183.1	
10		Extra carriage and difference of material rates				
a	14.50	Extra Carriage for cement	MT	Annex	299.08	
b	3.45	Extra Carriage for fine sand	cum	Annex	256.8	
c	17.48	Extra Carriage for coarse sand	cum	Annex	355.17	
d	17.28	Extra Carriage for crusher 11.2	cum	Annex	365.67	
e	17.28	Extra Carriage for crusher 13.2	cum	Annex	319.02	
f	5.44	Extra Carriage for stone ballast	cum	Annex	323.97	
g	2.439	Extra Carriage for steel	MT	Annex	227.25	

Notes:-

- These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from Jamsheer/ablowlal store (As per Availability).
- Any error regarding description, reference to CSR, Quantity, rate, premium, unit, calculations omission, addition will be corrected at any stage as per CSR, AOR, Specification and drawings and no claim whatsoever shall be entertained on this account.
- PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
- For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
- GST will be applicable as per Govt. norms and will be paid extra.
- Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.
- At the time of final billing, the merit position w.r.t actual work done shall be prepared again and total payment to be paid to the contractor shall be restricted as per cost percentage w.r.t. departmental rates of L-1 in revised comparative statement and approved comparative statement. In case if the merit position of L-1 contractor changes, the total payment to contractor will be restricted to L-1 Cost of revised comparative statement.

Signature of vendor